ESTIMATE

Hammer Time Home Improvement HIC#0668980 281 Middle Tpke E Manchester, CT 06040 860hammertime@gmail.com +1 (860) 830-7982 facebook.com/860hammertime



Bill to

Satish Kulkarni 1006 Sandstone Drive South Windsor, CT 06074 Ship to
Satish Kulkarni
1006 Sandstone Drive
South Windsor, CT 06074

Estimate details

Estimate no.: 721

Estimate date: 06/09/2025 Expiration date: 07/09/2025

#	Date	Product or service	Description	Amount
1.			Repair treads and risers on the set of stairs leading to 2nd floor of residence.	
			Remove drywall from under stairs to expose stair framing. Remove and replace any damaged stair framing and/or wedges. Add wood blocking to stair stringers to support treads. Wood blocks will be glued and screwed. Fasten treads to wood blocking using glue and screws. Treads will be fastened from below as to not damage the front surface of the material. Install cleats for drywall. Install 1/2in drywall to the underside of stairs where drywall was removed. Tape and sand drywall smooth in preparation to paint. Install crown moulding around perimeter where new drywall meets walls. Prime and paint ceiling and crown moulding with flat white ceiling paint.	
2.			Dryer duct replacement. Remove entire length of existing flexible dryer ductwork and hood. Install new 4in solid aluminum duct. Install new vent hood (Vent hood will be left white). Seal all seams in duct with aluminum tape. Attach to dryer with 4in hose clamp.	

Estimate includes all materials, labor, and disposal fees to complete the above mentioned work unless otherwise noted.

\$3,800.00

Total \$3,800.00	
	Expiry
07/09/2025	date

Accepted date

Accepted by